

At this location is a gabled ell Folk Victorian dwelling with Italianate influence, built ca. 1890. The house has a brick foundation, a gabled roof of asphalt shingles, an interior central brick chimney and an exterior of weatherboard siding. On the main (W) façade is a shed roof porch with wrought iron columns and handrails, concrete block piers with wood slat infill and a wood floor. The main entrance has a three-light, glass and wood door with an original, single-light glass and wood sidelight. On the north façade is a shed roof bay window with decorative brackets and cornice and original, two-over-two double hung wood sash windows. On the main façade are arched wood cornices with brackets, wood lintels, two-over-two vertical-light and two-over-one double hung arched wood sash windows.



At this location is a one-and one-half story side-gabled Craftsman dwelling built ca. 1930. The house has a continuous brick and poured concrete foundation, a roof of asphalt shingles, an exterior wall brick chimney and an exterior of narrow-width weatherboard siding. The house has a side gable roof with two small projecting gables on the main (E) elevation. Between the gables is a shed roof porch enclosed with square brick columns, a weatherboard exterior, six-over-one double hung wood sash windows and a nine-light glass and wood door. Poured concrete steps lead to the entrance with original brick rails with concrete caps and a ca. 1955 wrought iron railing. Leading from the porch to the main entrance is an original, Craftsman-style, nine-light glass and wood door flanked by original four-light glass and wood sidelights. Windows are original, six-over-one double hung wood sash. Other windows include nine-light casements and three-light fixed windows. At the roofline are knee brace brackets.



At the rear is an original frame garage with a clipped gable roof of asphalt shingles, horizontal wood siding and a sixteen-panel overhead track garage door. **Contributing**



115 Dundee - Contributing

At this location is a two-story, frame, gabled ell Folk dwelling built ca. 1910. The house has a continuous concrete block and stucco foundation, a gabled roof of asphalt shingles, an interior central brick chimney and an exterior of aluminum siding. On the main (W) façade is a shed roof porch enclosed with vinyl siding and one-over-one double hung wood sash windows. The main entrance to the porch has brick steps and wrought iron handrails and has a single-light glass and wood door with an aluminum storm door. Leading into the house from the porch is an original, glass and wood door. Windows are original, one-over-one double hung wood sash with simple corniced wood surrounds and flanking wood shutters. At the basement level are original, three-light awning wood windows.



At this location is a two-story, rectangular American Foursquare dwelling built ca. 1915. The house has a continuous brick foundation, a hipped roof of asphalt shingles, an interior central brick flue and an exterior of weatherboard siding. On the main (E) façade is a full-width, hipped roof porch enclosed with vinyl siding, one-over-one double hung vinyl sash windows, wood stairs and a spindle railing. The exterior door has an original, two-light etched glass and two-wood panel door. Windows are one-over-one wood sash with wood surrounds and are sited asymmetrically on the side facades. On the main façade is a gable dormer with a fixed three-light window. On the rear façade is a hipped roof porch enclosed with vinyl siding and one-over-one double hung wood sash windows and a large wood deck with wood rails and lattice panels.

At the rear is a ca. 1945, two-bay garage with a hipped roof, vinyl siding and two, ca. 1970 twenty-panel metal overhead track doors. **- Noncontributing**





At this location is a two-story, frame, gabled ell Folk dwelling built ca. 1910. The dwelling has a stuccoed foundation, a gabled roof of asphalt shingles, an exterior end main façade brick chimney and an exterior of aluminum siding. On the main (W) façade is a shed roof porch enclosed with aluminum siding, one-over-one double hung wood sash windows and an exterior aluminum storm door. Leading from the porch to the house is an original, two-light, glass and wood door. Windows are original, one-over-one and six-over-six double hung wood sash with wood surrounds. On the south façade is a projecting bay with a hipped roof, an exterior of aluminum siding and one-over-one double hung wood sash windows. Also on the south façade is a large single-light picture window. The basement has original, three-light awning glass and wood windows.

To the rear of the dwelling is an original, two-bay garage with a gable roof of asphalt shingles, an original five-panel wood pedestrian door and two, original, twenty-four wood panel overhead track doors. **- Contributing**





200 Dundee Avenue - Contributing (ARC Case 05-20)

At this location is a one-and one-half-story gabled Folk dwelling with Tudor Revival influence, built ca. 1915 and is known to have been moved to this location sometime before 1924. The house has a stone veneer foundation, a multi-gabled roof of asphalt shingles, an interior central brick chimney and an exterior of aluminum siding. On the main (E) façade is an incised shed roof porch with arched openings, square wood columns and engaged columns and a cut stone floor and foundation. The main entrance retains its original, six-light and four-wood panel door with an aluminum and glass storm door. Windows are original, eight-over-eight and six-over-six double hung wood sash with flanking wood shutters. In the gable fields are fixed louvered vents. On the rear façade is an original, shed roof wing with six-over-six double hung wood sash windows and a poured concrete foundation.



To the rear of the dwelling is a ca. 1935, single-bay garage with a gable roof of asphalt shingles, original, four-horizontal wood panel overhead track doors and an exterior of aluminum siding. **Contributing**



203 Dundee Avenue - Contributing ARC Case 02-35

At this location is an 1894 house that has recently become a bed and breakfast, the Barrington House. This asymmetrical Folk house has a cut stone foundation, a hipped roof of sawn cedar shingles with copper ridge runners, two interior central brick flues and an exterior of brick veneer. The main (W) façade has a projecting hipped roof porch with replacement Tuscan columns. The main entrance is an original four-light and three-paneled wood door with an original three-light transom and one-light and one-panel sidelights. At the rear is a hipped roof addition with a cut stone foundation and brick veneer siding. The windows throughout are one-over-one wood sash with wood surrounds and stone sills and lintels.











Boys sit in cow pasture which later became Station Street. Houses in background face on Dundee Avenue. Three were moved there from outside of town.

P. 80, Tales of Old Barrington




At this location is a two-story, side-gabled Queen Anne-influenced duplex built ca. 1894. The house has a continuous stone foundation, a roof of asphalt shingles and an exterior of brick veneer. On the main (W) façade are similar, single-story, shed roof porches with replacement square wood posts and railings and wood floors. A two-story projecting gable bay on the west facade divides the two units. Windows are one-over-one double hung wood sash with simple wood surrounds. In the gable fields are louvered vents and weatherboard siding. On the south façade is a secondary entrance with a concealed door and on the rear façade is a large, original wing with an exterior of aluminum siding, a poured concrete foundation and arched basement windows with single-light awning windows.



At this location is a two-story, frame gabled ell Folk dwelling built ca. 1910. The house has a continuous stone foundation, a gable roof of asphalt shingles, an exterior wall brick chimney and an exterior of weatherboard siding. On the main (E) façade is a single-story shed roof porch. The porch appears to have been enlarged and enclosed for use as a sunroom ca. 1955. Windows on the porch are ca. 1970, one-over-one double hung wood sash design. A ca. 1970, nine-light glass and wood door serves as the entrance to the porch. Leading into the main house from the porch is a two-square-light and four-wood panel door. Windows in the dwelling are ca. 1970, six-over-six double hung wood sash and have original simple wood cornices and surrounds. On the main façade gable section is a hipped roof bay window with a central, fixed,

fifteen-light window flanked by six-over-six double hung wood sash windows. On the north elevation is a ca. 1970, one-story frame flat roof addition with a poured concrete foundation and an exterior of weatherboard siding. A porch on the rear elevation was also enclosed ca. 1970.

To the southwest of the dwelling is a ca. 1950, frame storage shed with a shed roof of asphalt shingles and an exterior of horizontal board. - **Noncontributing**





At this location is a two-story, frame, gabled ell Folk dwelling built ca. 1910. The house has a continuous stone veneer foundation, a gabled roof of asphalt shingles and an exterior of vinyl siding. On the main (E) façade is a projecting gable roof canopy supported by wrought iron brackets, with a poured concrete stoop and wrought iron handrails. Originally the dwelling had a partial-width, single-story porch on the main façade but this was enclosed ca. 1970 with a triple set of ten-over-one vertical-light double hung wood sash windows and a second story added with a shed roof. The upper level has a single-light picture window flanked by one-over-one metal windows. The main entrance has a ca. 1950, four-inset-wood-panel door with an aluminum storm door. The windows are original, ten-over-one and eight-over-one vertical-light, Craftsman-style double hung wood sash with wood surrounds. On the main façade is a hipped roof bay window added ca. 1970 with aluminum siding and a twelve-over-one window flanked by eight-over-one vertical-light double hung wood sash windows and supported by a brick base.



Off the southwest corner of the dwelling is a ca. 1945, large, single-bay garage with a hipped roof, an exterior of



aluminum siding and an original, sixteen-wood panel overhead track and a shed roof lean-to off the north facade. **– Noncontributing**



216 Dundee Avenue – Noncontributing (ARC Case 05-16)

Located at 216 Dundee Avenue is a two-story, gable front dwelling built ca. 1910 but extensively altered in the late 20th century. The house has an stone veneer covered continuous foundation, a gable and shed roof of asphalt shingles, an exterior end and an interior central brick chimney and an exterior of aluminum siding. On the main (E) façade is a partial-width porch enclosed with aluminum siding and a second story added ca. 1970. The main entrance has a ca. 1990, nine-light and two-panel metal door with original, five-light glass and wood sidelights. On the first floor of the south façade is a hipped roof oriel supported by wood brackets with three, single-light fixed windows.

At the rear is a ca. 1910 hipped roof one-bay garage with aluminum siding and cross-hatched hinged wood double doors. **- Noncontributing**





At this location is a two-story gable front dwelling built ca. 1915 and either totally replaced or drastically altered ca. 1985 with the addition of vinyl siding, stone veneer and one-over-one double hung vinyl sash windows. On the main (E) façade is a bay window with a hipped roof, three, one-over-one double hung vinyl sash windows and a vinyl base. The main entrance has a ca. 1990, six-panel metal door with a storm door above which is a hipped roof canopy. A stone veneer, poured concrete stoops leads to the main entry.



At this location is a two-story, frame, gable front Folk dwelling built ca. 1915. The house, formerly a wing of the Hough Street School (as was 316 Dundee Avenue), has a continuous poured concrete foundation, a gable roof of asphalt shingles, an exterior end chimney covered in vinyl and an exterior of vinyl siding. The full-width porch was enclosed and a second story added with a hipped roof ca. 1945 with a triple set of one-over-one double hung metal window on the first floor and two, paired sets of one-over-one double hung metal sash windows on the second story. Vinyl siding was added later. The main entrance has a ca. 2000, six-panel metal door with an inset wood panel transom and single-light and single wood panel sidelights. Above the entrance is a canvas awning and leading up the doorway is a spindled wood railing and stone walkway. Windows are one-over-one double hung wood sash with flanking vinyl shutters. A projecting hipped roof bay on the south façade has no windows only vinyl siding. Also on the south facade are two octagonal vinyl windows, one on the first floor and one on the second

floor. Above a triple set of windows on the main facade

is a dentiled and bracketed wood lintel.

To the northwest of the dwelling is a ca. 1960, two-bay garage with an exterior of vinyl siding, a gable roof of asphalt shingles, one-over-one double hung wood sash windows and two, metal overhead track doors.

Noncontributing



At this location is a two-story, frame, gable front Italianate dwelling built ca. 1910 and extensively altered in the late 20th century. The house was at one time a wing of the Hough Street School, (as was 308 Dundee Avenue) and has a continuous rock-faced concrete block foundation, a gable roof of asphalt shingles, an exterior end and an interior brick chimney and an exterior of aluminum siding. On the main (E) façade is a two-story, enclosed porch with aluminum siding and three, centrally located, single-light glass and aluminum windows with flanking metal shutters. The main entrance is located in this enclosure and has a ca. 1990, nine-light glass and two-metal panel door with flanking full-length metal shutters. Windows are original, one-over-one double hung wood sash. The house has a wide eave with simple paired brackets. A secondary entrance on the south elevation has an original, single-light glass and wood door with a hip roof canopy supported by wrought iron posts.



At the rear of the dwelling is an original, frame garage with a hipped roof of asphalt shingles, an exterior of aluminum siding and no visible doors. - **Contributing**